

ISTITUTO GIORDANO

Via Rossini 247814 BELLARIA (RN) Italy Tel. ++39/0541 343030 (10 lines) Telefax ++39/0541 345540

e-mail: istitutogiordano@giordano.it web site: www.giordano.it

Tax Code/VAT N°:00 549 540 409 Chamber of Commerce (RN) N° 156766 Rimini Company Register N° 00549540409 Company capital E 516,000.00 entirely paid up

OFFICIAL ACKNOWLEDGEMENTS:

MINISTRY OF PUBLIC WORKS, Law 1088/71 with Ministerial Decree D.M. 27/11/82 N° 22913 "Tests on

Ministerial Discrete IV 27/11987. N° 22/913 Tests on building materials IV 27/11987. N° 22/913 Tests on building materials Decrete DM 09/91199 "EC certifi-cation for an uniformative DM 09/91199 "EC certifi-cation for an uniformative DM 19/9199 "EC Certifi-tation of the stand emission of building after Certification of the stand emission of building after canacture."

nes"
MINISTRY OF INDUSTRY COMMERCE HANDICRAFTS Law Decree D.L. 27/01/92 N° 136 "EEC certification of the sound emissions of earth moving

tification of the sound emissions of earth moving machines?

MINISTRY OF INDUSTRY COMMERCE HANDICRAFTS Ministerial Decree D.M. 08,070.9 "EEC certification concerning the safety of toys."

MINISTRY OF INDUSTRY COMMERCE HANDICRAFTS. Ministerial Decree D.M. 90,079.9" EEC certification and conformity statements for the «fifuency of hot water boilers fired with liquid or geneous fuels."

MINISTRY OF INDUSTRY COMMERCE HANDICRAFTS. Notification N° 757390 "EEC certification for ass acciliances."

CRAFTS Notification NY 757390 "EEC certification for gas appliances" in ININISTRY OF INDUSTRY COMMERCE HANDI-JORFTS and MINISTRY OF LABOUR AND SOCIAL PARTS and MINISTRY OF LABOUR AND SOCIAL SECURITY. Ministerial Decree D. M. 0907/83" "EEC certification concerning simple pressurised vesself MINISTRY OF LABOUR AND SOCIAL SECURITY Ministrat Decree D. M. 04/09/04 "EEC certification of mechanes".

MINISTRY OF INDUSTRY COMMERCE HANDI-GRAFTS. "Verification assignments concerning the

CRAFTS: Verification assignments concerning the safety and conformity of products in relation to market surveillance and consumer safeguards."

MINISTRY OF INDUSTRY COMMERCE HANDICRAFTS. Ministerial Decree D.M. 02/04/98 "Issue of
certificates of conformity for the energy specifications
and performances of the components in buildings and

sate performances of the Components in Deutings at Systems' STEP INTERIOR. Law 818/84 and Ministerial Decree D.M. 2003/95 with authorisation 2/100/96 Fire issection tests according to Ministerial Decree D.M. 2000/94* MINISTRY OF THE UNIFICIAL Ministerial Decree D.M. 2003/95 with authorisation 100/7/96 Fire resistance tests according to Groular 91 of 14/00/95.

91 of 14/00/81*

MINISTRY OF THE INTERIOR: Law 918/94 and filminerial Decise D.M. 28/03/95 with authorisation of 16/07/92 Fire resultance tests according to Circular N° 7 of 02/04/91 and standard CNIVE/FICE UNI 97.25*
MINISTRY OF THE INTERIOR Law 918/94 and himsterial Decise D.M. 28/03/95 with authorisation of 12/04/93 "Tests on portable fire extinguishers according to Ministrial Decise D.M. 20/12/92"
MURST (MINISTRY OF UNIVERSITIES AND SCIENTIFIC AND TECHNOLOGICAL RESEARCH). Law 46/92 with Ministrial Decise D.M. 09/10/95*
"Admission to the rolls of laboratories authorised to conduct applied research in favour of small and medium sized industries".
BINISTRY OF PUBLIC EDUCATION: Protocol N° 116 of 27/03/81 "Registration with the National research Registry File sitt dools N° EGMYSY?"
SINCERT (Accrediting of Cartification Bodies):
Accreditation N° 03/74 of 19/12/00 "Quality system certification body".

SINCERT (Accrediting of 14/11/91
STIT (Calibration Service in Italy). Accreditation N° 20 CSTI Calibration centure for thermometric and electrical Transport tests concerning Product Certification Plans". 91 01 14/05/01 MINISTRY OF THE INTERIOR: Law 818/84 and

Plans*
IMO (Quality Mark Institute) "Laboratory tests concerning Product certification plans for flues"
IMO (SAU (Mark Institute) "Laboratory tests concerning Product certification plans for flues"
IMO (SAU) (Markonal Union of Aluminium Swell Alicy
frame makers) Activa-ok-glement of 28/03/55"
"Laboratory for UNICGAU, certification tests on door
and window frames and curtain valids"
UNI (Italian National Standardizing Body - Certification
Sactisty Laboratory tests concerning Froduct certification plans for wood freplaces with fluid in forced circulation and external discr and window frames".

ASSOCIATION MEMBERSHIPS

AIA: Italian Acoustics Association.
AICARR Italian Association of Air Conditioning.

and Administrators

EARTO: European Association of Research and
Technology Organisation.

EGOLF: European Group of Official Laboratories for

Fire Testing.
UNI Italian National Standardising Body

This document refers to the tested sample or material only. This document cannot be partially duplicated without written authorisation from the laboratory

TEST REPORT N° 174823)

Place and date of issue: Bellaria, 27/08/2003

Principal: BEMO SYSTEMS Gmbh & Co KG - Karl-Henschel-Strasse, 7 -

72770 REUTLINGEN-BETSINGEN (GERMANY)

Date on which test was requested: 04/07/2003

Number and date of job order: 22814, 07/07/2003

Date on which sample was received: 24/07/2003

Date on which test was conducted: from 25/07/2003 to 25/08/2003

Subject of the test: Test for watertightness of the metal roofing element

Testing place: Istituto Giordano S.p.A. - Test field of Via San Mauro -

47814 Bellaria (RN)

Origin of sample: supplied by Principal

Denomination of the sample*.

The sample tested consists of a tunnel containing a portion of "BEMO" metal roofing and mainly consists of:

- portion of "BEMO" roofing;
- bearing structure.



(*) according to the Principal's declaration and inspections made by the Institute's technical personnel

Stamp of

This test report consists of 14 pages

Page N° 1 of 13



The portion of roofing consists of:

- 3 (three) "BEMO Normal Profil 65/500 1" panels 9840 mm in length;
- modified "BEMO panel 9840 mm in length and with female turn-up at the ends;
- modified "BEMO" panel 9840 mm in length with male turn-up at the ends;
- 36 "BEMO Halter 80/6" supports made of aluminium alloy.

The panels are made of 1 mm thick aluminium alloy and are connected together at the top of the end turn-up by means of male/female profiles formed by bending the metal plate. The male profile has an elastomer seal which holds the panels together.


The portion of roofing made with the panels described above is borne by 36 "BEMO - Halter 80/6" supports made of aluminium alloy.

The end sections of the portion of roofing, consisting of three standard profiles and the two modified profiles, are closed with a sealing sheath so as to form a retaining trough borne by the wooden structure. These end sections are approx. 520 mm in length and are not considered in relation to the test results as the watertightness could be impaired by the sheath-panels connection.

The bearing structure consists of two longitudinal beams made of laminated wood measuring 100 x 520 x 10040 mm and a series of wooden cross-members measuring 80 x 100 mm in section. The cross-members and beams are connected together with galvanised steel sheet brackets and self-threading screws.


The sample is illustrated in the following drawings and photographs.








DETAIL 1: MODIFIED PANEL WITH FEMALE END TURN-UP



DETAIL 2: MODIFIED PANEL WITH MALE END TURN-UP






DETAIL 3: PANEL COUPLING ON A LEVEL WITH THE END TURN-UPS

Female profile

Seal


Male profile








DETAIL 5: SUPPORT-PANEL CONNECTION



DETAIL 6: CHANNEL CASING







Photograph of the sample subjected to the test



Photograph of the sample subjected to the test:

Detail of the connection between the panels and panelssupport.





Photograph of the sample subjected to the test:

Detail of the connection between the lower cross-members and longitudinal beams.

Test equipment:

The following equipment was used for the test:

- bearing structure of the sample;
- metric rod to check the level of the water on the sample;
- water source;
- absorbent felt pads for the tightness test.





Test method and development.

The sample was installed flat on the bearing structure and was then given a covering able to prevent variations in the level of water in the trough caused by evaporation or rainfall. he test then started and developed during the following operating phases:

- water was poured into the trough so as to form a 150 mm head in relation to the flat surface of the panels. This head was maintained for 7 days, during which the intrados area of the panels was visually inspected each day on a level with the joints to check whether water was present either in the form of drops or whether it had simply wetted the surface itself. Accurate tightness tests were conducted at the end of the first and seventh day of the test with the 150 mm head, by passing pads of absorbent paper along the slits on a level with the joints between the panels;
- water was added to the trough so as to form a 200 mm head in relation to the flat surface of the panels. This head was maintained for 7 days, during which the intrados area of the panels was visually inspected each day on a level with the joints to check whether water was present either in the form of drops or whether it had simply wetted the surface itself. Accurate tightness tests were conducted at the end of the first and seventh day of the test with the 200 mm head, by passing pads of absorbent paper along the slits on a level with the joints between the panels;
- water was added to the trough so as to form a 300 mm head in relation to the flat surface of the panels. This head was maintained for 17 days. During the first seven days with the 300 mm head, the intrados area of the panels was visually inspected each day on a level with the joints to check whether water was present either in the form of drops or whether it had simply wetted the surface itself. Accurate tightness tests were conducted at the end of the first, the seventh and the seventeenth day of the test with the 300 mm head, by passing pads of absorbent paper along the slits on a level with the joints between the panels;

A portion of the roofing was taken at the end of the test, on a level with a support, so as to check the coupling between the panels and connection to the supports.

The test is illustrated in the following photographs.








The sample during the test.



Intrados of the sample during the test with a 300 mm head.





The sample during the test with a 300 mm head.







A sample is taken of the roofing.

Test results.

No water was found on the intrados surface of the sample either near or on a level with the joints between the panels, neither during the visual inspection nor during the test with absorbent pads.



The Test Technician in Charge (Dr.Eng. Giovanni Capitani

Engineering Laboratory Manager Dr.Eng. Giovanni Capitani The Chairman or Managing Director Dr.Eng Vincenzo Iommi